

2017 Medina County Item 422 MC3000 Chip Seal Bid

Bid Tabulation

Bid Opening Date: 1:30 P.M. - August 4, 2017

Medina County Highway Facility

6100 Wedgewood Road, Medina, Ohio 44256

Contractor's Bid Blank – Firestone Road – C.H. 26

From: State Route 224

To C.H.83:Black River School Road

ADTs: 530 to 709

Length: 10,629 (Feet)
Width: 20.0 (Feet)
Area: 23,620 (Sq. Yds.)

Length: 2.01 (Miles)
Repair Rate: 0 (Cu. Yds./Mile)
Aggr. Rate: 20 (Lbs/SY)
MC3000 Rate: 0.40 (Gals/SY)

Melway Paving Co., Inc.
7571 State Route 83
Holmesville, OH. 44633
330-279-9000

Item	Quantity	Units	Item Description	Unit Cost	Total Cost	Unit Cost	Total Cost
422	9,448	Gals	MC300 Seal Coat Applied at 0.40 Gals/SY	\$1.50	\$14,172.00	\$1.50	\$14,172.00
422	236	Tons	No. 8 ACBF Slag Cover Aggregate Applied at 20 Lbs/SY	\$73.00	\$17,228.00	\$73.00	\$17,228.00
614	1	Lump Sum	Traffic Control – Chip Seal Course	\$2,000.00	\$2,000.00	\$1,350.00	\$1,350.00
614	2.01	Miles	Work Zone Center Line, Class 2	\$400.00	\$804.00	\$400.00	\$804.00
Total Proposal 1 – Firestone Road:					\$34,204.00		\$33,554.00

Contractor's Bid Blank – Proposal 2 – Sanford Road – C.H. 102

From: Pawnee Road – C.H. 28

To: Congress Road – C.H. 29

ADTs: 658 to 950

Length: 6,294 (Feet)
Width: 19.0 (Feet)
Area: 13,287 (Sq. Yds.)

Length: 1.19 (Miles)
Repair Rate: 0 (Cu. Yds./Mile)
Aggr. Rate: 20 (Lbs/SY)
MC3000 Rate: 0.40 (Gals/SY)

Item	Quantity	Units	Item Description	Unit Cost	Total Cost	Unit Cost	Total Cost
422	5,315	Gals	MC300 Seal Coat Applied at 0.40 Gals/SY	\$1.50	\$7,972.50	\$1.50	\$7,972.50
422	133	Tons	No. 8 ACBF Slag Cover Aggregate Applied at 20 Lbs/SY	\$73.00	\$9,709.00	\$73.00	\$9,709.00
614	1	Lump Sum	Traffic Control – Chip Seal Course	\$1,200.00	\$1,200.00	\$800.00	\$800.00
614	1.19	Miles	Work Zone Center Line, Class 2	\$400.00	\$476.00	\$400.00	\$476.00
Total Proposal 2 – Sanford Road:					\$19,357.50		\$18,957.50

Contractor's Bid Blank – Proposal 3 – Zimmerman Road – C.H. 30

From: Jeffrey Road – C.H.111

To: State Route 224

ADTs: 219 to 308

Length: 12,942 (Feet)
Width: 20.0 (Feet)
Area: 28,760 (Sq. Yds.)

Length: 2.45 (Miles)
Repair Rate: 0 (Cu. Yds./Mile)
Aggr. Rate: 20 (Lbs/SY)
MC3000 Rate: 0.40 (Gals/SY)

Item	Quantity	Units	Item Description	Unit Cost	Total Cost	Unit Cost	Total Cost
422	11,504	Gals	MC300 Seal Coat Applied at 0.40 Gals/SY	\$1.50	\$17,256.00	\$1.50	\$17,256.00
422	288	Tons	No. 8 ACBF Slag Cover Aggregate	\$73.00	\$21,024.00	\$73.00	\$21,024.00

2017 Medina County Item 422 MC3000 Chip Seal Bid

Bid Tabulation

Bid Opening Date: 1:30 P.M. - August 4, 2017

Medina County Highway Facility

6100 Wedgewood Road, Medina, Ohio 44256

			Applied at 20 Lbs/SY				
614	1	Lump Sum	Traffic Control – Chip Seal Course	\$2,500.00	\$2,500.00	\$1,862.00	\$1,862.00
614	2.45	Miles	Work Zone Center Line, Class 2	\$400.00	\$980.00	\$400.00	\$980.00
Total Proposal 3 – Zimmerman Road:					\$41,760.00		\$41,122.00

Contractor's Bid Blank – Proposal 4 – Holshoe Road – C.H. 82

From: State Route 301

To: Pawnee Road – C.H. 28

ADTs: 208 to 225

Length: 13,433 (Feet)

Length: 2.54 (Miles)

Width: 19.0 (Feet)

Repair Rate: 0 (Cu. Yds./Mile)

Area: 28,359 (Sq. Yds.)

Aggr. Rate: 20 (Lbs/SY)

MC3000 Rate: 0.40 (Gals/SY)

Item	Quantity	Units	Item Description	Unit Cost	Total Cost	Unit Cost	Total Cost
422	11,344	Gals	MC3000 Seal Coat Applied at 0.40	\$1.50	\$17,016.00	\$1.50	\$17,016.00
			Gals/SY				
422	284	Tons	No. 8 ACBF Slag Cover Aggregate	\$73.00	\$20,732.00	\$73.00	\$20,732.00
			Applied at 20 Lbs/SY				
614	1	Lump Sum	Traffic Control – Chip Seal Course	\$2,500.00	\$2,500.00	\$1,700.00	\$1,700.00
614	2.54	Miles	Work Zone Center Line, Class 2	\$400.00	\$1,016.00	\$400.00	\$1,016.00
Total Proposal 4 – Holshoe Road:					\$41,264.00		\$40,464.00

Total Amount Proposals 1-4

\$136,585.50

\$134,097.50